

2. Each bidder shall before he is permitted to bid be required to furnish a solvency certificate as under the Tangadi Sale Rules and deposit a sum of Rs. 50 (rupees fifty) as earnest money with the officer conducting the sale; the deposit will be returnable to him at the close of the sale if his bid is not accepted. The person whose bid is accepted shall immediately after the close of the sale pay 25 per cent of the bid amount less the deposit already paid, failing which, the right will be resold or worked departmentally at the risk of the defaulting bidder. He will be liable for the loss, if any, that may result by such resale or departmental working which will be recoverable from him as arrears of Land Revenue, but he shall not participate in any gain.

3. Defaulters to the department will not be allowed to bid at the sale.

4. All timber yielding trees marked by the department will be sold kindvar for a lump-sum amount for the whole coupe.

5. Power is reserved to the Range Forest Officer to accept or reject any bid without assigning any reason therefor.

6. Within a week from the date of intimation regarding the confirmation of the sale the person whose bid is accepted, shall deposit a sum of Rs. 50 (fifty) or 25 per cent of the sale amount whichever is less for each coupe as security towards the due fulfilment of his contract. He shall also pay within that period the remaining 75 per cent of the contract amount due by him and shall execute an agreement, on a stamped paper of proper value, accepting the above terms and the terms specified below, failing which, the amount already paid will be forfeited to Government and the produce resold or worked departmentally at his risk as noted in clause (2) *supra*. The security deposit or the balance thereof as may remain over shall be repayable to the contractor on his producing proof relieving him of any liability under the contract.

The following are the further conditions to which the contractor should bind himself:—

(a) That he shall fell and remove the timber trees purchased by him before the 15th June 1931.

(b) That he shall make the fellings of the trees in a methodical manner from one side of the coupe.

(c) That each consignment of timber shall be covered by a passport issued by the Range Officer or any other officer-deputed by the District Forest Officer in this behalf.

(d) That if any tree, shrub, or growth reserved by the department is cut, he shall pay a fine not exceeding Rs. 10 per tree.

(e) That he shall abide by the rules of the department as regards the kindling of the fire and shall hold himself responsible for any forest offences committed by his agents, employees or workmen.

(f) That no operation shall take place in the forest after sunset and before sunrise.

(g) That he shall not sublet the contract to anybody except with the written sanction of the District Forest Officer.

(h) That he shall have no right whatsoever over the coupe and over the timber paid for but left unremoved in any of the coupes after 30th June 1931.

(i) That he shall maintain a register in the form prescribed by the District Forest Officer showing the number of trees felled and the outturn of fuel resulting therefrom and shall keep it open for the examination of the Forest Officers above the grade of guards.

(j) That for any breach of any of the conditions of the contract by the contractor or his agents, the contract shall be void at the option of the District Forest Officer and that the latter may, after issuing the contractor a notice of the cancellation of the contract enforce forfeiture of all or any part of the deposit and shall resell the right or work it departmentally at the risk of the contractor as in clause (2) *supra*. If the deposit or part thereof is so forfeited, it shall be immediately made good by the contractor.

MAHOMED PIR,
District Forest Officer.

ENGINEERING DEPARTMENT.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Notification dated 27th September, 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer, Bangalore, up to 2 P.M. on 31st October 1930, for constructing:

1. A Transformer Station,
2. A combined Office and Stores,
3. Four blocks of Operators' quarters,
4. Three blocks of cooly quarters,
5. Seven blocks of latrines,

at Chikballapur Town.

1. The tenders will be opened in public at 2 P.M. on 31st October 1930. The work should be completed within 6 months and the monthly progress should be not less than Rs. 6,000.

2. The quantities given are approximate and the plans, detailed estimates and the conditions may be seen at the Chief Electrical Engineer's Office, Bangalore, on all working days during the office working hours.

3. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for constructing Electrical buildings at Chikballapur Town" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Electrical Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender, the successful tenderer will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful tenderer, will be posted on the notice board in the Chief Electrical Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The construction work should be started within a week from the date of the notification of the acceptance.

10. Water for construction should be got at the contractor's own expense.

11. Specifications for works are those recognised by the Mysore Public Works Department and Marryat's specifications.

12. The contractor should be bound by the conditions of the Schedule of contract of the Electrical Department.

Statement showing the approximate quantities of work for constructing a Transformer Station.

No.	Items of work	Unit	Quantity	Rate
1.	Earthwork excavation and filling in basement including lead of 50 feet.	C.yd.	70	Rs. a. p.
2.	Levelling ground and facilitating drainage	L. S.	...	
3.	Stone jelly in lime mortar, concrete foundation	C.ft.	637	
4.	Masonry stone in the lime mortar, foundation and basement.	"	1,270	
5.	Burnt brick in lime mortar superstructure	"	3,274	
6.	Stone slabs 6" thick undressed	S.ft.	161	
7.	Stone slabs exposed parts one line dressed	"	24	
8.	Chunam plastering two coats	Sqr.	49.33	
9.	Chunam pointing with thread lines	"	1.94	
10.	White and colour washing two coats	"	51.20	
11.	Bed slabs of trusses and I beams with 2 bolt holes fixed complete 2' x 1½' x 6"	Each	8	
12.	Flooring with 9' sgr. first class Mangalore tiles on 6" stone jelly in lime mortar concrete and cement pointed.	Sqr.	7.92	
13.	Roofing with 22 B. W. G. corrugated galvanized iron sheeting with ½" thick pine wood ceiling or ½" thick teak wood planking sheets to overlap 12" at ends and two corrugated at sides.	"	8.64	
14.	Do do without ceiling	"	5.30	

No.	Items of work	Unit	Quantity	Rate
				Rs. a. p.
15	Ridge sheeting 22 B. W. G. plain galvanized iron sheeting two feet wide.	R.ft.	41	
16	Teakwood work with wood oiling two coats	C.ft.	51.25	
17	Teakwood door panelled with bolts, hinges, etc., complete including tarring to frames as per drawing No. G. 231.	S.ft.	60	
18	Teakwood windows glazed with iron bars $\frac{3}{4}$ " dia. with hinges, etc., complete including tarring to frames as per Drawing No. G. 231.	"	252	
19	Teakwood rectangular ventilators glazed with iron bars including tarring to frames as per drawing No. G. 231.	"	64	
20	Silicate painting two coats	Sqr.	19.16	
21	Steel trusses 24 ft. clear span fixed complete as per drawing No. G. 231.	No.	3	
22	Iron work fixed complete	Cwt.	27.00	
23	Balls 40 lbs. per yard fixed complete	"	16.18	
24	Providing openings and anchorages for incoming and outgoing lines (departmental).	"	...	
25	Electric lighting and water supply to Stores and Transformer Station (departmental).	"	...	

Constructing Combined Office and Stores.

1	Earthwork excavation and filling-in basement including a lead of 50 feet.	C.yd.	46	Rs. a. p.
2	Levelling site and facilitating drainage	L. S.	...	
3	Stone jelly in lime mortar, concrete foundation	C.ft.	479	
4	Masonry stone in lime mortar, foundation and basement.	"	819	
5	Burnt brick in clay superstructure	"	3,093	
6	Stone slabs 6" thick undressed	S.ft.	84	
7	Stone slabs 6" thick roughly dressed for pillars including cutting slots for bressemmers.	"	66	
8	Chunam plastering 2 coats	Sqr.	45.23	
9	Chunam pointing with thread lines	"	1.65	
10	White and colour washing 2 coats	"	46.88	
11	Flooring with Cu'dapah slabs $1\frac{1}{2}$ " thick on 3" stone jelly in lime concrete and cement pointed.	"	13.77	
12	Roofing with corrugated galvanized iron sheeting 24 B. W. G. with galvanized iron screws and washers, sheets to overlap 12" at ends and 2 corrugations at sides.	"	21.84	
13	Galvanized iron ridge sheeting 2 feet wide 22 B. W. G. with galvanized iron screws and washers.	R.ft.	52	
14	Honey wood door panelled frames 6"x4 $\frac{1}{2}$ " with bolts, hinges, etc., complete including tarring to frames as per drawing No. C. 108.	S.ft.	48	
15	Honey wood door panelled frames 5"x4" with bolts, hinges, etc., complete, including tarring to frames as per drawing No. C. 108.	"	64	
16	Honey wood windows glazed 1 $\frac{1}{2}$ " thick shutter frames 4 $\frac{1}{2}$ "x4" with iron bars 5/8" dia. with bolts, hinges, etc., complete, including tarring to frames as per drawing No. C. 108.	"	105	
17	Honey wood windows panelled 1 $\frac{1}{2}$ " thick shutter 4 $\frac{1}{2}$ "x4" frames with iron bars 5/8" dia. with bolts, hinges, etc., complete, with a pigeon hole at bottom and plank at sill including tarring to frames.	"	18	
18	Honey wood ventilators glazed with iron bars including tarring to frames as per drawing No. C. 108.	"	24	
19	Painting with 2 coats of chocolate paint.	Sqr.	16.21	
20	Wrought iron work fixed complete	Cwt.	61.86	

No.	Items of work	Unit	Quantity	Rate
<i>Constructing one Block of Cooly Quarters.</i>				
1	Earthwork excavation and filling in basement including a lead of 50'.	C.yd.	38	Rs. a. p.
2a	Lime mortar and stone jelly concrete foundation. (proportion of jelly to mortar 2 : 1 and the mortar to be 1 lime to 2½ sand.)	C.ft.	303	
b	Coursed rubble stone masonry in clay, foundation and basement.	"	847	
c	Burnt brick in clay, superstructure ...	"	2,460	
d	6" plain cornice built of brick in mortar and chunam plastered, etc., complete.	R.ft.	72	
e	Stone slabs 4" thick roughly dressed and set in mortar.	S.ft.	159	
f	Stone slabs 4" thick roughly dressed for stone pillars including cutting slots to bressummers.	"	26	
g	Chunam plastering 2 coats ...	Sqr.	53.74	
h	Chunam pointing with thread lines ...	"	1.01	
i	White and colour washing 2 coats ...	"	54.75	
j	Constructing sinks with drain pipes ...	Each	4	
k	Stone mortar pestle including fixing charges ...	"	4	
3	Flooring with 3" concrete and chunam plastered on top.	Sqr.	7.97	
4a	Roofing with 1st Class Mangalore tiles on teakwood reepers 2"x 1" including cement pointing and chunam borders at ends of roof wherever necessary.	"	11.40	
b	Ridge tiles set in mortar and cement pointed ...	R.ft.	22	
c	Ventilating tiles set in mortar and cement pointed...	Each	16	
5a.	Mattywood work wrought and put up with 2 coats of wood oiling.	C.ft.	41.71	
b	Galvanized iron sheet (24 B. W. G.) doors with teakwood frames, bolts, hinges, etc., complete (frame 4"x 3½").	S.ft.	78	
c	Galvanized iron sheet (24 B. W. G.) windows with iron bars and fittings, complete (frame 3½"x 3").	"	70	
d	Teakwood ventilators glazed with wire gauze shutters fixed, complete.	"	24	
e	Chocolate painting 2 coats ...	"	3.20	
6	Galvanized iron sheet sunshades with teak frames and painting.	Each	4	

Construction of one block of Latrine.

1	Earthwork excavation and filling in basement ...	C.yd.	4
2a	Stone in clay foundation and basement ...	C.ft.	130
b	Burnt brick in mortar superstructure ...	"	196
c	Chunam plastering ...	Sqr.	4.91
d	Chunam pointing ...	"	0.56
e	White and colour washing 2 coats ...	"	5.47
f	Cement plastering ½" thick ...	"	0.70
g	Tar washing 2 coats ...	"	0.63
3	Flooring with 3" concrete and cement plastering ½" thick.	"	0.38
4	Fixing outlets, constructing drains, etc. ...	Item	1 Item
5	Providing galvanized iron sheet tubs 12" x 6" x 6" with handles, etc., complete with tarring.	Each	6

Construction of a block of Operators' Quarters, to accommodate two families at Chikallapur.

No.	Items of work	Unit	Quantity	Rate
				R. s. a. p.
1	Earthwork excavation and filling in basement	Cyd.	51	
2a	Stone jelly in chunam mortar concrete foundations	C.ft.	583	
b	Stone in clay, foundation and basement	"	1,055	
c	Burnt brick in clay, superstructure	"	3,058	
d	Stone slabs 5" thick roughly dressed and set in mortar	"	217	
e	Do 4" thick roughly dressed and set in mortar.	"	24	
f	Chunam plastering two coats	Sqr.	61.87	
g	Chunam pointing	"	2.10	
h	Binding wall 1-1/8' x 9" brick in clay and chunam plastering.	R.ft.	50	
i	Plain cornice, 6" projection	"	50	
j	Constructing sinks complete	Each	5	
k	Providing mortar and pestle	"	2	
3	Flooring with 3" lime concrete and chunam plastering with a floating coat of cement.	Sqr.	8.79	
4a	Roofing with 1st Class Mangalore tiles on teak reepers 2" x 1" complete.	"	11.24	
b	Ridge tiles set in mortar and cement pointed	R.ft.	41	
c	Cuddapah slab terrace with cuddapah slabs 1 1/2" thick, 3" concrete and plastering on top complete.	Sqr.	3.20	
d	Burnt brick in mortar 9" projection	R.ft.	63	
e	Burnt brick in mortar parapet wall 1 1/2' high as per plan.	"	59	
5a	Matty wood work wrought and put up with two coats of wood oiling.	C.ft.	35.28	
b	Doors with teak frames and honney wood battened shutters 1" thick with iron fixtures.	S.ft.	240.50	
c	Window with teakwood frames and honney wood battened shutters 1" thick and iron bars 5/8" diameter complete.	"	96	
d	Honney wood planks 1" thick for shelves fixed on teakwood pegs complete.	"	48	
e	Chacolate painting two coats	Sqr.	12.18	
f	Expanded metal 3" x 1 1/2" x 1/8" mesh fixed on teakwood frames complete.	S.ft.	75	
6a	Roiled steel girders fixed complete (continental)	Cwt.	18.45	
b	Rain water down pipes 3' diameter fixed complete	R.ft.	20	

C. M. CARIAPA,
Chief Electrical Engineer.

KOLAR DIVISION.

Notice dated 26th September 1930.

The attention of the public is invited to the Notification published in the *Mysore Gazette*, Part VI, page 1170, dated 25th September 1930, calling for tenders for widening and retvetting the well in the Government Silk Farm at Kolar Taluk.

The latest date for tender is 18th October 1930.

Notice.

The attention of the public is invited to the Notification published in the *Mysore Gazette*, Part VI, pages 1168 to 1169, dated 25th September 1930, calling for tenders for restoring Siddaghatta tank, Mulbagal Taluk.

The latest date for tender is 18th October 1930.

N. LAKSHMINARASIMHAIA,
Executive Engineer.